



2

3-Port Non-vented



3-Port Non-vented, Fixed Setting



Counterbalance valves with pilot assist are meant to control an overrunning load. The check valve allows free flow from the directional valve (port 2) to the load (port 1) while a direct-acting, pilot-assisted relief valve controls flow from port 1 to port 2. Pilot assist at port 3 lowers the effective setting of the relief valve at a rate determined by the pilot ratio.

Other names for this valve include motion control valve and over-center valve.

TECHNICAL DATA

NOTE: DATA MAY VARY BY CONFIGURATION. SEE CONFIGURATION SECTION.

Pilot Ratio	3:1		
Maximum Recommended Load Pressure at Maximum Setting	215 bar		
Maximum Setting	280 bar		
Factory Pressure Settings Established at	30 cc/min.		
Maximum Valve Leakage at Reseat	0,3 cc/min.		
Adjustment - No. of CCW Turns from Min. to Max. Setting	3.75		
Reseat	>85% of setting		
Locknut Hex Size	15 mm		
Locknut Torque	9 - 10 Nm		
Seal kit - Cartridge	Buna: 990011007		
Seal kit - Cartridge	EPDM: 990011014		
Seal kit - Cartridge	Polyurethane: 990011002		
Seal kit - Cartridge	Viton: 990011006		

CONFIGURATION OPTIONS

Model Code Example: CBCALHN

CONTROL	(L)	FUNCTIONAL SETTING RANGE (H)	SEAL MATERIAL	(N)	MATERIAL/COATING
 L Standard Screw Adjustment C Tamper Resistant - Factory Set 		 H 1000 - 4000 psi w/25 psi Check (70 - 280 bar w/ 1,7 bar Check), 3000 psi (210 bar) Standard Setting A 1000 - 4000 psi w/4 psi Check (70 - 280 bar w/ 0,3 bar Check), 3000 psi (210 bar) Standard Setting B 400 - 1500 psi w/4 psi Check (28 - 105 bar w/ 0,3 bar Check), 1000 psi (70 bar) Standard Setting 	N Buna-N E EPDM V Viton		Standard Material/Coating /AP Stainless Steel, Passivated /LH Mild Steel, Zinc-Nickel

I 400 - 1500 psi w/25 psi Check (28 -105 bar w/ 1,7 bar Check), 1000 psi (70 bar) Standard Setting